

## SECTION 1100

### DETOURING/TRAFFIC CONTROL

#### 1.00 GENERAL

1.01 Scope. This work shall consist of furnishing, installing, moving, maintaining and removing temporary traffic signs, advance warning signs, barricades, channelizing devices, delineators, and flagmen as required by the latest revision of the "Manual on Uniform Traffic Control Devices for Streets and Highways" and the latest revisions of the Colorado Supplement thereto, in accordance with the Drawings and these Specifications.

1.02 Related Work Specified Elsewhere.

All Sections.

1.03 Reference Standards.

A. State of Colorado, Division of Highways S-Standards, Sheets S-614-50 (pages 1-4), and S-614-51.

B. "Manual on Uniform Traffic Control Devices for Streets and Highways". MUTCD

1.04 Submittals.

A. Submit a "Traffic Control Plan" to the Town for acceptance prior to construction.

1.05 Field Conditions. The traffic control through the construction areas is the responsibility of the Contractor. The Contractor's "Traffic Control Plan" shall include the proposed methods of handling traffic for each of the different stages of construction within the guidelines of this Specification. The Contractor will prepare a schedule of traffic control devices necessary for each anticipated and identified construction operation. Control devices may be used at more than one location.

Approval of the proposed method of handling traffic shall constitute authorization to furnish the devices on the schedule. If, at any time, it is determined that unnecessary units are on the schedule or that additional units are required, the Town will furnish the Contractor with a revised schedule of authorized devices. Any change in the plans or the method of handling traffic shall be approved by the Town. Approval of the proposed method of handling traffic in no way shall relieve the Contractor of liability specifically provided for in the Contract. Before proceeding with construction, the Contractor shall have written approval from the Town of the proposed method of handling traffic.

#### 2.00 MATERIALS

2.01 General. All materials shall conform to the applicable portions of the Reference Standards.

#### 3.00 METHODS AND PROCEDURES

3.01 General. All methods and procedures shall conform to the approved "Traffic Control Plan" including all approved revisions.

3.02 Flagmen. Provide as needed, as directed by Engineer or as stated on Drawings to control traffic encroaching in construction zone.

3.03 Barricades, Flashing warning Lights. Provide for all open trenches, equipment and material storage, etc., and as called for on the Drawings and located within limits of construction. Protection to be in place 24 hours per day.

End of Section